

INNOVAAS × PDUMIND.

Intelligent Rack PDU Solutions

Metered, switched, and 3-phase power distribution units for AI infrastructure, high-density data centers, and HPC environments worldwide.

PRODUCT LINES

CPDU Series — Intelligent Rack PDUs

Single-phase & 3-phase · Metered & Switched · Up to 48 outlets · TFT display · SNMP v1/v2c/v3

CM-V-3P16A-36C39-3M — 3-Phase Monitoring PDU

380–433Vac · 16A · 11.5kW · 36×C39 · Schneider breaker · Hot-swap meter

CM-V-3P16A-1806-3M — 3-Phase Distribution PDU


380–433Vac · 16A · 18×C13 + 6×C19 · Aluminum 1U · IPDU control head

CM-V-3P32A-1806-3M — 3-Phase High-Current PDU

380–433Vac · 32A · 18×C13 + 6×C19 · Aluminum 1.4U · Heavy-duty 32A industrial plug

PRODUCT OVERVIEW

CPDU Series — Intelligent Rack PDUs



Single-phase and three-phase IPDU smart meter products built on PDUmind's innovative **SUM** (Sustainable, Upgradable, Maintainable) design concept. Active metering for energy optimisation and circuit protection with user-programmable alarm thresholds — real-time local and remote alerts for potential circuit overloads.

AI CLUSTERS

HPC

HYPER-SCALE DC

COLOCATION

IDC

FINANCE & BANKING

GOVERNMENT

ENTERPRISE

KEY FEATURES

01

Energy-Efficient Latching Relays

Bi-stable latching relays consume up to 70% less energy than alternatives. In case of PDU failure, power distribution to the rack is maintained.

02

PDU Cascading — Up to 16 Units

Daisy-chain up to 16 PDUs from a single IP address via Cat5/6 cable, dramatically reducing network port requirements in large deployments.

03

±1% Billing-Grade kWh Accuracy

Enables precise allocation of data center energy expenses with billing-grade ±1% metering accuracy per outlet or phase.

04

IEX Universal Combo Socket

UL and IEC tested C13/C19 combo socket accepts C14 or C20 plugs. Alternating phase on 3-phase systems helps balance load across branches.

05

Dual Gigabit Ethernet Ports

World's first dual GbE port PDU. Share monitoring between data center management systems and end clients across two separate networks.

06

Advanced Security

256-bit AES encryption · RADIUS · SNMP v3 · SSHv2 · SSL · HTTPS. Supports the most stringent data center security requirements.

07

RCM Residual Current Monitoring

Optional BENDER RCM module measures ground wire current, reducing risk of electric shock and simplifying regulatory auditing.

08

Hydraulic-Magnetic Circuit Breakers

Not affected by ambient temperature. Proactively monitors breaker status and sends overload alerts before a tripped circuit causes downtime.

PLATFORM CAPABILITIES

Feature Category	Details
Screen Display	OLED / TFT Multi-Colour Screen with push-button interface (Up / Menu / Down / Reset)
Alerts & Metrics	Live alarms and power metrics — V, A, PF, W, kWh per outlet or phase
Network Connectivity	Dual Gigabit Ethernet ports + optional Wireless LAN adapter
Mobile Integration	iOS compatible — IECView App
Configuration	Flash drive bulk configuration · Web UI · Telnet CLI
Reboot Functionality	Reset button for full electronics reboot without interrupting power output

TECHNICAL SPECIFICATIONS

CPDU Series — Electrical & Physical Parameters



Category	Parameter	Value
Electrical Parameters		
INPUT VOLTAGE	AC Input	176-264 VAC, 1-Phase or 3-Phase
INPUT CURRENT	Maximum	63 A / 80 A (model dependent)
FREQUENCY	AC Frequency	50 / 60 Hz
OUTPUT OUTLETS	Maximum	Optional – up to 48 outlets
CIRCUIT BREAKER	Protection	Optional (specify brand and quantity)
Physical / Structure		
INSTALLATION	Orientation	Vertical (standard)
FORM FACTOR	Width	1U and 1.5U and above
SOCKET PROTRUSION	Height	22 mm
SHELL MATERIAL	Enclosure	Plastic PC
METER DIMENSIONS	Controller head	153 × 44.5 × 22 mm
Working Environment		
OPERATING TEMP	Ambient	-10 °C to +50 °C
HUMIDITY	Working	5-95 % RH (non-condensing)
ALTITUDE	Max	0-3,000 m
User Interface		
DISPLAY	Screen type	TFT colour screen
CONTROLS	Buttons	Up · Down · Menu · Reset
INTERFACES	Ports	Ethernet × 1 · RS485 × 2 · USB × 1
ENV. SENSOR	T/H Interface	YES – cascable up to 8 EMD sensors
INDICATORS	LED Status	Operation · Electrical energy · Communication
Measurement & Control		
PDU TOTALS	Measurements	Voltage · Current · Power · Electrical energy (kWh)

3-PHASE DISTRIBUTION & MONITORING PDUS

CM-V Series

The CM-V series are vertical rack-mount, 3-phase intelligent distribution PDUs built from 1U/1.4U aluminum extrusion profiles. Each unit ships with a 3-metre IEC60309 industrial power cord and integrates a hot-swappable IPDU meter head for total detection of voltage, current, power, and energy consumption. Hydraulic-magnetic circuit breakers provide IT-grade overload protection on every branch.



CM-V-3P16A-36C39-3M — Monitoring IPDU (36 × C39 Outlets)

Parameter	Specification	Parameter	Specification
RATED VOLTAGE	380–433 Vac	OUTPUT VOLTAGE	220–250 Vac
FREQUENCY	50/60 Hz	OVERLOAD PROTECTION	1P 16A Schneider Breaker
INPUT PLUG	IEC60309 16A 3-phase industrial	MAX OUTPUT CURRENT	16 A
CABLE	3G × 2.5 mm ² × 3 m	OUTPUT RECEPTACLES	36 × C39
MAX POWER	11.5 kW	DIMENSIONS (W×D×H)	1910 × 56 × 44.5 mm
MAX INPUT CURRENT	16A 3-phase	CASE MATERIAL	Aluminum · Black
MAX CIRCUIT CURRENT	16 A	WARRANTY / ROHS	1 year / RoHS compliant

Monitoring Functions — CM-V-3P16A-36C39-3M

DISPLAY (HOT-SWAP METER)	MONITORING FUNCTIONS	ACCESS & ALARMS
Voltage: FS 300V, ±1%	Total load current	Web UI (HTTPS)
Current: FS 32A, ±1%	Total input voltage	SNMP v1/v2c/v3
Energy: 0.1 kWh res.	Total load power	Telnet CLI
Temp: 0.1°C res.	Electricity consumption	Email alarm
Humidity: 0.1% res.	Temp & humidity	SNMP trap

CM-V-3P16A-1806-3M & CM-V-3P32A-1806-3M — Distribution PDUs

Parameter	CM-V-3P16A-1806-3M	CM-V-3P32A-1806-3M
INPUT VOLTAGE	380–433 V 50/60 Hz	380–433 V 50/60 Hz
INPUT PLUG	IEC60309 6-core 16A industrial	IEC60309 5-core 32A industrial
INPUT CABLE	5G × 2.5 mm ² × 3 m	5G × 6 mm ² × 3 m
MAX CURRENT	16 A	32 A

WHY INNOVAAS

Authorized Reseller — Southeast Asia & Beyond

Authorized PDUMind Reseller

Innovaas is an officially authorized reseller for PDUMind intelligent rack PDUs across Southeast Asia. Direct manufacturer access means competitive pricing and accurate technical guidance.

Global Availability

All products are available for worldwide delivery. Our team coordinates customs documentation, freight forwarding, and logistics to your data center location.

Pre-Sales Technical Support

Our engineers assist with topology reviews, outlet count planning, phase balancing calculations, and compatibility with your existing power infrastructure.

Custom Configuration

PDUMind's modular architecture supports custom outlet counts, breaker specifications, cable lengths, and outlet types. Contact us with your requirements.

PRODUCT SUMMARY

Model	Type	Phase	Max Current	Key Feature
CPDU Series	Intelligent Rack PDU	1PH / 3PH	63A / 80A	Per-outlet metering, SNMP, cascade 16
CM-V-3P16A-36C39-3M	Monitoring IPDU	3-Phase	16A	36×C39, hot-swap meter, Schneider MCB
CM-V-3P16A-1806-3M	Distribution PDU	3-Phase	16A	18×C13 + 6×C19, aluminum 1U
CM-V-3P32A-1806-3M	Distribution PDU	3-Phase	32A	18×C13 + 6×C19, aluminum 1.4U, 32A plug

ORDERING & CONTACT

Get a Quote or Request Samples

SALES ENQUIRIES

sales@innovaas.co

WEBSITE

innovaas.co/solutions/data-center-power

MANUFACTURER

PDUMind · www.pdumind.com

LEAD TIME

Standard stock items: 2–4 weeks
Custom configurations: 4–8 weeks

MINIMUM ORDER

Single unit available
Volume pricing from 5+ units

WARRANTY

1 year standard
Extended warranty available

To place an order or request a quotation: email sales@innovaas.co with your model number(s), quantity, outlet configuration, input voltage, and delivery location. Our team will respond within one business day with pricing and lead-time confirmation.